40 YEARS IN NATION BUILDING

NCC

LETTER OF AWARD (LOA)

Ref No: NCCL/Hardoi/SWSM-UP-DN/2021/13 **Date: 03-04-2022**

To,
M/S ARYA CONSTRUCTIONS,
Plot No - 504,
Hind Nagar,
Kanpur Road, Lucknow
Uttar Pradesh – 226012
GST No:- 09BVWPS9044N1ZB
Email ID:- pawan007666@gmail.com
Contact No:-+91- 9452382818

Kind Attn. Mr. Pawan Kumar Singh

Sub:- Earthwork, lowering, laying, jointing, hydro-testing, civil works and commissioning of HDPE/DI & MS Distribution Pipe line along with Functional Household Tap Connections Network in Hardoi District Reg.

Dear Sir,

With reference to above subject and Subsequent discussions had with you at our site Office, Hardoi District. We are pleased to issue the LOA for carrying out Distribution Network in our water works, Hardoi District.

The detailed work order with scope of work and terms and conditions were mentioned in Annexure-II & Rates for Distribution Network works is attached in Annexure-I.

Please revert back with your acceptance for further necessary actions from our end.

Thanking You

Yours Faithfully

For NCC Limited **Accepted by**

Authorized Signatory **Proprietor**

Annexure-II

Terms & Conditions

NCC Scope:- Supply of HDPE pipes/ butterfly valve / sluice valve / air valve / dismantling joint/ GI pipe, saddle & tap-up to NCC stockyard.

Agency Scope: -

Shifting, loading & unloading of pipes from NCC stockyard to site, all fittings /specials & any other items required for laying. Supply of any other tools and jointing machine testing equipment for hydraulic test.

Scope of Work:

The work is to be executed as per the design, drawings, specifications approved by the department and as per the agreement conditions of RFP and to the satisfaction of the TPI/DWSM/SWSM officials as per Annexure-I.

Time Period:

All the machinery / tools / safety barricading / manpower / Consumable etc., required for the above works are in your scope of work. This work order is being issued based on your assurance for laying of minimum 20Km per month and 10Km Hydro-testing per Month.

Quality:

All the HDPE works should be carried as per SWSM specifications confirming IS 4984-2016. In case any defects observed at site the same should be rectified by you. Immediately failing which we will be forced to get the same rectifications done directly or by third party and the corresponding expenditure shall be debited to you. All the debit notes deemed accepted if no objection raised from your end at each RA bill certification stage by our engineer/accounts-in-charge, you should maintain all equipment and testing apparatus is good in good condition with latest calibration certificates and insurance from time to time wherever applicable.

Note:-

Labour accommodation, food & transportation is in agency scope. Quantity per GP may vary up to any extent

Terms and Conditions:

A. Payment Terms: -

Excavation cannot be done by more than 1 KM without laying and jointing. Payment will be done for actual work done QTY certification of Site Engineer / Project Manager for every fifth kilometer billing the first kilometer should be hydro-tested. The payment shall be released as below:

1. Excavation and Laying of pipes	65%
2. Gap Closing	10%
3. Hydrostatic testing incl. water	15%
4. Commission of pipe line	10%

The contractor has to submit monthly RA bills in suitable formats to Engineer for Verification and certification on 25th – 30th of every month. 90% amount shall be released to party within 15 days from date of certification by NCC Engineer / Client.

B. Taxes and Duties:

I. We agree to pay GST Extra @12% as applicable on above rates.

II. You have to submit GST invoices along with your RA bills for reimbursement of tax to you. You shall upload the GST tax invoice and File Returns within the time prescribed under the GST Act and submit necessary proof or availing input Tax Credit by us.

III. In case of any credit refund or other benefit is denied or delayed to NCC LIMITED due to non-compliance by you (such as failure to upload the details of sale on GST Portal failure to pay GST to government or due to non-furnishing of or furnishing of incorrect or incomplete documents) then you should reimburse the loss along with its interest and penalty.

IV. TDS shall be deduced as per prevailing rules and certificate shall be issued accordingly.

V. You shall provide all the necessary documents while accepting the work order.

C. Storage, Safe Custody & Protection to Works:

You shall be responsible for the safe custody, protection and security of all materials, construction tools and tackles, machinery at site, etc. which are covered under this contract. You shall take necessary action to protect all finished or partially finished

works executed by you till the time of Joint Measurement Report (JMR) along with all completion of hand-over, as well as ensure that no damages are inflicted on the works executed by other agency or to any other property / structure during the course of execution of your works. All costs incurred on making good such damages shall be recovered from your account.

D. General Conditions: -

I. Unloading of Pipes at site received from Stockyard, Shifting of Pipes, Specials, Valves from NCC Central Stores / Zonal Stores to your work location and security of materials, trench excavation for pipelines in all types of soils (Manual/ Mechanical) including display of safety boards and barricading the traffic.

II. Minimum cover of 1 Meters depth shall be maintained above the pipe top level while laying.

III. Laying the pipe line true to alignment and gradient, barricading and fixing of all bends, specials, valves etc., complete.

IV. Refilling Trenches with excavated earth (other than rocky & boulders) with watering, tamping and carting of excess soil as directed by Engineer-in-Charge.

V. Hydro-testing of the pipe line laid includes cost of water etc., complete as per departmental direction & commissioning.

VI. Re-shifting of excess pipe & valves and other specials from site to the nearest NCC stock yards.

VII. Materials & Consumables: DI & HDPE Pipe & Specials, Valves etc., should be reconciled at every bill and if any shortage, the cost of materials will be debited from your RA Bill. Along with RA Bill reconciliation statement certified by our engineer shall be submitted by you without which the bill will not be accepted for verification.

VIII. Water and Electricity has to be arranged by you for your requirement. Any statutory deposits or payment to be made to any agency has to be borne by you.

IX. The work will be inspected by TPIA/DWSM/SWSM/NCC Engineers at different stages of work and you are bound to rectify the bad quality of works if any noticed by clients / consultants.

X. You should not damage any of our Employer property during execution of job and you are responsible for damage to any property of the public / private / under & above ground utilities / our-selves, the same will be rectified by you at your cost.

XI. No ideal Charges will be paid against men & machineries under any circumstances.

Note: - Pipe, Specials & Valves etc., will be supplied by NCC at their Central / Zonal stockyards (Shifting of the same to your work location from the stockyard of NCC is in your scope.

E. Commercial Conditions:

i. Retention money @ 10% will be deducted from your Bill. Retention money will be released after completion of defect liability period of 12 months or the same can be released after completion of work against submission of Bank Guarantee (BG) for equivalent amount valid for 12 months.
ii. The rates agreed shall remain firm till completion of total scope of work and no price escalation is allowed.
iii. All the Consumables required to execute the job is at your cost only.
iv. Hire charges for the construction equipment supplied by company if any will be debited to your account at current market rates.
v. Contractor has to make suitable arrangements for his site office and labour camp and maintain the premises in hygienic way following COVID protocols from the authority time to time.

F. Work Completion & Liquidated Damages:

Entire scope of work shall be completed within stipulated period of time and schedule. In case you fail to execute the awarded job with in the given time period, we will have the right to either cancel the work order without prejudice to any other rights or make alternate arrangements for completion of job. The expenses incurred by us will be accountable to you only. In case of delay penalty of 1% per week shall be imposed, subject to maximum 5% of value of work order.

G. Defect Liability Period:

Entire Scope of work shall be covered under Defect Liability of 12 months after completion of all work satisfactorily. If any defect is found during liability period due to poor workmanship / material, agency will rectify it within seven days and if not attended the same, NCC will get it rectified from another agency at the risk and cost of vendor.

40 YEARS IN NATION BUILDING

NCC

H. Mode of Measurement:

The payment will be made on the basis of actual measurements of the works duly certified by the Site Engineer/TPI/Client.

OUR GST NO VALID INUP: 09AAACN7335C1ZN

You shall indicate your CIN No, in all your invoices / DC etc., without fail.

For NCC Limited

(G.V.K.RAJU)

Accepted by

Proprietor

Annexure-I					
Name of the Project :- Hardoi					
S.No	Description	Unit	Rate	Quantity	Total Amount
1	Earthwork excavation for pipe line and rising main and Distribution system trenches including lift up to 1.5 m and lead up to 50m and refilling, watering, ramming of the excavated earth into the trench and also disposal of surplus earth upto 50m from the center of the trenches including supply of all material, labour, T&P etc, required for proper completion of works as per direction of the Engineer. Lowering, laying, Jointing of Pipes (excluding loading at yard) and including inter-carting from stockyard and unloading at work sites of various sizes of pipes for distribution system conforming to latest/ relevant I.S. 4984/1995 Specifications with all jointing materials and specials conforming to latest /relevant I.S. specifications, including barricading, shoring and strutting, danger lighting and using sight rails and boning rods at every 100 mtr. Pipe Joints shall be water tight with laying true to alignment and gradient and jointing etc. complete (including testing of pipe lines and cutting of pipes for making up the length) all complete as per instructions of Engineer-in - charge. (DI & HDPE Pipes & Fittings, DI/HDPE specials, Gaskets will be provided by NCC at Zonal/Central stock yard) Cost including all machinery and equipment, all tools & tackles and hydro test at site as per is 4985 or any latest IS code of Practice or 1.5 times rated pressure whichever is higher with the water supplied with all leads and lifts for hydro testing of Pipeline shall be provided by contractor at his own cost.				
	HDPE Pipes (PE-100)-PN-6				
1.1	63 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	60.00	14,016.23	840,973.89
1.2	75 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	60.00	9,639.76	578,385.82
1.3	90 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	62.00	6,785.23	420,684.16
1.4	110 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	62.00	4,449.46	275,866.62
1.5	125 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	65.00	2,178.50	141,602.34
1.6	140 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	69.00	1,890.64	130,453.88
1.7	160 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	75.00	2,026.05	151,953.92
1.8	180 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	85.00	813.25	69,126.15
1.9	200 mm dia HDPE Pipe PN-6: Class PE-100	Rmt	90.00	1,382.41	124,417.32
2	Labour charges for fixing of Double Flange Sluice valves/Scour Valves, Sluice Valve Type Fire Hydrant including Valve fittings and dismantling joints and including collection and shifting of Valves from site stores to work site, lowering them into already prepared trenches, fixing in position, Jointing with pipe lines. And testing etc. including manpower, consumables. transporting and intercarting, tools and tackles complete with all leads and lifts, as per specifications and drawings and as directed by the Engineer-in-charge for finished item of work. Required quantity of Valves, Specials, Nuts, Bolts and Gaskets shall be issued by NCC at free of cost at their Central/Zonal Stock yards.				

Annexure-I					
Name of the Project :- Hardoi					
S.No	Description	Unit	Rate	Quantity	Total Amount
2.1	**Sluice Valves**				
2.1.1	Sluice valve - 300mm dia	Nos	500.00	1.00	500.00
2.1.2	Sluice valve – 250 mm dia	Nos	400.00	3.00	1,200.00
2.1.3	Sluice valve – 200 mm dia	Nos	400.00	5.00	2,000.00
2.1.4	Sluice valve -150 mm dia	Nos	350.00	10.00	3,500.00
2.1.5	Sluice valve -125 mm dia	Nos	350.00	10.00	3,500.00
2.1.6	Sluice valve – 100 mm dia	Nos	350.00	10.00	3,500.00
2.1.7	Sluice valve – 80 mm dia	Nos	300.00	10.00	3,000.00
2.2	**Scour Valve**				
2.2.1	Scour valve -80 mm dia	Nos	300.00	3.00	900.00
2.2.2	Scour valve -100 mm dia	Nos	350.00	3.00	1,050.00
2.2.3	Scour valve -150 mm dia	Nos	350.00	3.00	1,050.00
2.2.4	Scour valve -200 mm dia	Nos	400.00	3.00	1,200.00
2.2.5	Scour valve -250 mm dia	Nos	400.00	3.00	1,200.00
	Labour charges for fixing of Kinetic type double orifice valves including collection and shifting of valves from site store to work site, lowering them into already prepared trenches, fixing in position, jointing them with pipe lines and testing etc., including manpower, consumables, transportation /inter carting, tools and tackles etc., complete with all lead and lifts and as per specifications, drawings and as directed by the Engineer-in-charge for finished item of work. Required quantity of valves, Specials, Nut Bolts and Gaskets shall be issued by NCC at free of cost at Central/Zonal Stock yards.				
	Air Valve				
3.1	20 mm	Nos	250.00	2.00	500.00
3.2	50 mm	Nos	250.00	2.00	500.00
3.3	80 mm	Nos	250.00	2.00	500.00
3.4	150mm	Nos	250.00	2.00	500.00
4	Labour charges for fixing of underground sluice valve type fire hydrant consisting of 80 mm dia sluice valve, 80mm dia tail pieces, 80mm dia duck foot bend and 80 mm dia standard makes iron coupling with cap and etc. complete conforming to latest/relevant specifications and drawings and proper finishing of work and lowering them into the already prepared trenches, fixing in position and jointing them with pipelines and testing etc. complete as per instructions of Engineer-in - charge. Required quantity of valves, Specials, Nut Bolts and Gaskets shall be issued by NCC at free of cost at Central/Zonal Stock yard.				
I	80 mm	Nos	500.00	6.00	3,000.00
5	Construction of following type chambers as per department type design and drawing including RCC perforated Manhole Cover, labour, T&P etc complete for proper completion of work as per instructions of Engineer - in-charge. Cement/Reinforcement Steel shall be Provided by NCC at free of cost at their Central/Zonal stock yards.				

Annexure-I					
Name of the Project :- Hardoi					
S.No	Description	Unit	Rate	Quantity	Total Amount
5.1	**Sluice valve chamber (masonry Type)**				
5.1.1	Dia up to 200mm-1000(L)x1200(w)x1300(H)mm	Nos	9,000.00	20.00	180,000.00
5.1.2	Sluice valve chamber(surface box Type)	Nos	2,000.00	29.00	58,000.00
5.1.3	Fire hydrant chamber(750(L)x450(W)x1000(H)mm)	Nos	7,000.00	6.00	42,000.00
5.2	**Air Valve Chamber**				
5.2.1	350(L)x350(W)x500(H)	Nos	2,000.00	8.00	16,000.00
5.3	**Scour Valve Chamber**				
5.3.1	Dia up to 200mm-1000(L)x1200(W)x1300(H)	Nos	9,000.00	15.00	135,000.00
5.4	**PVR Valve Chamber**- 1000(L)x1200(W)x1300(H)	Nos	9,000.00		
6	Dismantling of Following type of surfaces including sorting out and stacking of serviceable materials and disposal of unserviceable materials up to a distance of 50m as per instructions of Engineer -in -charge.				
6.1	B.O.E surface	Sqm	42.00	5,328.07	223,779.02
6.2	Bituminous Surface	Sqm	42.00	1,281.14	53,807.94
6.3	Interlocking Road	Sqm	52.00	332.22	17,275.70
6.4	C.C Road	Sqm	180.00	2,413.88	434,497.94
7	Reinstatement of the following type of road surface with old and new materials including supply of all materials, labour T&P etc. required for proper completion of the work as per instruction of Engineer-in-charge.				
7.1	B.O.E surface (50% of existing bricks to be reused)	Sqm	150.00	5,328.07	799,210.79
7.2	Bituminous surface	Sqm	1,050.00	1,281.14	1,345,198.60
7.3	Interlocking Road	Sqm	450.00	332.22	149,501.23
7.4	C.C Road	Sqm	850.00	2,413.88	2,051,795.81
8	Culvert crossing-along the alignment of pipe line complete as per instructions of Engineer -in charge and as per the standard drawing. MS Pipe and MS Clamp, Cement shall be issued by NCC at stock yard on Free issue basis				
8.1	Nalla/ Culvert Crossing (width-3.5 m) upto Dia 300 mm		3,000.00	6.00	18,000.00
9	Road Crossing- Excavation foundation of trench of proper size in soil mixed with moorum, Shingle, Kankar, soft rock, hard rock, including refilling, dressing and ramming earth or sand or bajri, ballast, including providing. carting, lowering, laying and jointing of casing pipe of RCC NP-3 with appropriate size, with rubber ring joint, sand filling in gap inside RCC pipe, insertion of distribution pipe into the encasing pipe including supply of T&P, including concrete of 150 mm thick in with 40mm gauge brick ballast local sand and cement in proportion of 8:4:1, provision for barricading, labour for traffic diversion etc .Complete for proper completion of work as per instruction of Engineer. **Only Cement/Steel shall be issued free by NCC at Stock yard.(Hume Pipe is in Agency Scope)**				
9.1	50 mm dia . Pipe	Rmt	700.00	100.00	70,000.00
9.2	100 mm dia . Pipe	Rmt	800.00	300.00	240,000.00
9.3	150 mm dia . Pipe	Rmt	950.00	20.00	19,000.00
9.4	200 mm dia . Pipe	Rmt	1,250.00	10.00	12,500.00
9.5	250 mm dia . Pipe	Rmt	1,650.00	10.00	16,500.00
9.6	300 mm dia . Pipe	Rmt	2,100.00	10.00	21,000.00
9.7	350 mm dia . Pipe	Rmt	2,250.00	10.00	22,500.00

Annexure-I					
Name of the Project :- Hardoi					
S.No	Description	Unit	Rate	Quantity	Total Amount
9.7	400 mm dia . Pipe	Rmt	3,100.00	10.00	31,000.00
9.8	600 mm dia . Pipe	Rmt	3,450.00	10.00	34,500.00
10	Labour Charges for Making house connection should be done at least 2 m inside the boundary wall with provision of tap from distribution line to outer wall of house, 1m G. I. pipe (15 mm) (above ground) & average 5 mtr. MDPE Pipe (20 mm) (below ground) including specials, saddle, Tap, etc. backfilling, laying and jointing for proper completion of suitable size, T&P etc. including excavation & work as per instructions of Engineer as per Dwg- 12 (excluding road restoration). All House connection materials, Cement, Reinforcement Steel shall be free issue by NCC at their Central/Zonal Stock yards	Nos	500.00	2,000.00	1,000,000.00
	Grand Total				**9,752,131**
Amount Ninety seven Lakhs fifty two thousand and one hundered thirty one Rupees Only					
Note:- Quantities & amount mentioned are approximatley and Payment shall be made as per actual quantities executed at site					

For NCC Limited

(G.V.K.RAJU)

Accepted by

Proprietor